



Timberlane Regional High School
Track & Tennis Court
Renovation Project

NCPA Bid Proposal

Revised
5/25/2018



May 7, 2018

Thomas Geary – Business Operations Coordinator
SAU 55
30 Greenough Rd
Plaistow, NH

**NCPA Bid Proposal
Running Track & Tennis Court Renovations
Plaistow, NH**

Running Track Renovation

Prices are based on the NCPA (National Cooperative Purchasing Alliance) program. NCPA provides competitively solicited pricing for preferred products and services. Because these products and services have been bid at a national level, individual public entities do not need to duplicate their own bid process.

Please Note: It is the opinion of Cape & Island Tennis & Track that the existing surface cannot be resurfaced again, despite looking like it might be reasonable to do so. This type of surface needs to breath to allow vapor to escape. Once surface reaches a certain age and has been previously recoated, embedded silt and organic materials, plus the additional coatings have reduced its porosity. Therefore we recommend surface replacement when the surface becomes no longer acceptable for its intended use.

Option 1: Surface Replacement & Asphalt Overlay Method

General: This proposal is for the complete replacement of the existing running track surface from all surfaced areas (track, high jump, horizontal jumps and pole vault) located at Timberlane Regional High School in Plaistow, NH. Included in this option is the removal and disposal of the existing track surface, the installation of a 1.25" asphalt overlay, and the installation of a new upgraded track system.

Cape & Island Tennis & Track to Provide:

- Remove & dispose of the existing synthetic surface from track and field events.
- Clean existing asphalt base.
- Make repairs to existing asphalt base where necessary.
- Cut out approximately 400sf of high jump apron and replace subbase materials.
- Patch with 3" of bituminous concrete.
- Install asphalt tack coat prior to overlay.
- Install 1.25" bituminous concrete overlay to running track oval and high jump and runways.
- Install 3" bituminous concrete pavement to pole vault and long jump runways.

- Install 1 in-ground takeoff tray system per runway (2 total). Triple jump lines to be painted.
- Install 1 new in-ground stainless steel pole vault plant box.
- Install Maroon **BSS-100** polyurethane paved mat structural spray system (an IAAF certified product), manufactured by Beynon Sports Surfaces of Hunt Valley, MD.
- Install NFHS certified line markings.
- Project shall be managed by an **ASBA Certified Track Builder**
- “As Built” layout drawing for striping

Price for Running Track Renovation: **\$312,875**
For Running Track Renovation Initial Here: _____

Deduct Alternate – Black Plexitrac Lighting

In lieu of Maroon polyurethane system, CIT&T will provide and install a black 1/2” Plexitrac Lightning (water-based) all-weather track surface.

Deduct Alternate for Black Surface Installation: <\$65,350>
For Black Surface Alternate Initial Here: _____

Option 2: Track Surface Installation Only

In lieu of Turnkey Option 1, Cape & Island Tennis & Track will supply and install track surface installation only.

Price for Blue BSS-100 polyurethane track system: **\$197,800**
For BSS-100 Surface Initial Here: _____

Price for Black Plexitrac Lighting track system: **\$132,450**
For Plexitrac Lighting Surface Initial Here: _____

Tennis Court Renovation

Cape & Island Tennis & Track is pleased to present the following proposal for the installation of four post tensioned concrete tennis courts at Timberlane High School HS in Plaistow, NH. Prices are based on the NCPA (National Cooperative Purchasing Alliance) program. NCPA provides competitively solicited pricing for preferred products and services. Because these products and services have been bid at a national level, individual public entities do not need to duplicate their own bid process.

Please Note: This tennis court proposal is for installation during the summer/fall of 2018, based on project specifications.

- I. Rebuild existing 208’ x 120’ courts in post tensioned concrete including new net posts, nets, 4 coat Plexipave surface and game striping – includes **25 year warranty** against structural cracking.

NCPA Co-Op Price: \$213,879.46 (\$77.12 per square yard)

Additional Work Required:

- II. Remove and dispose of existing fencing, net posts and footings
- III. Pulverize existing asphalt.
- IV. Layout new court, augment sub base with additional material as needed, compact and laser grade to .83% slope

Price: \$37,578.00

- V. Furnish and install new 1 3/4" black fusion bonded 9 gauge tennis fencing at 10' high with 2 gates

Price: \$39,360.00


Price for Tennis Court Renovation: **\$290,817**
For Tennis Court Renovation Initial Here: _____

Price does not include any landscaping or additional work outside the footprint of the courts.

Payment Schedule to be as Follows:

Upon approval of agreed upon schedule of values, payment shall be made according to completion of scheduled items bi-monthly.

Balance to be paid upon completion.

Authorized Signature:  Date: 5 / 17 / 2018
Kristoff Eldridge, CTB
Vice President – Track Division

Acceptance of Quote

If the foregoing meets with your acceptance, kindly sign and return the attached copy of our proposal. Upon its receipt it is understood the foregoing, including the terms and conditions set forth above, will constitute the full and complete agreement between us.

Authorized Signature: _____ Date: ____/____/____

This quote expires thirty days from the date hereof, but may be accepted at any later date at the sole option of Cape & Island Tennis & Track.